


SURECAV SYSTEM


COPYRIGHT SURECAV LTD. © 2015

FOR MORE INFORMATION VISIT WWW.SURECAV.CO.UK

NOTE: Addition wall ties when building away from reveal

Ref: Teplo 1 type tie by Ancon Ltd.

This procedure will prevent slots having to be made in the SureCav sheet on each course of blockwork when building away from a doorway or window reveal. It is recommended that an additional wall tie is included within 225mm of the opening on each board course level to satisfy the structural requirements. The ties should then be fitted every 450mm vertically coinciding with the joint in the SureCav sheet.

| | | | | |
|--|---|---|---|-------|
| UNITS | DO NOT SCALE | PROJECTION | Additional wall ties when building away from reveal | TITLE |
| DIMENSIONS mm UNLESS OTHERWISE STATED | THIS IS A CAD DRAWING AND MUST NOT BE CHANGED MANUALLY |  | | |
| | | | SURECAV DETAIL WITH TEPLO TIES | |